

SCHOOL OF PLANNING AND ARCHITECTURE: NEW DELHI
4, Block – B, I.P. Estate, New Delhi – 110 002

Ref. No.: F.1-73/11-12/SPA(PSM)

December 19, 2011

Date of opening: 27.12.2011 at 03:00 p.m.

NOTICE INVITING QUOTATION

Name of work: A/R & M/O ELECTRIC SUB – STATION OF ARCHITECTURE BUILDING, SPA, NEW DELHI (ESTIMATED COST: Rs.30,666/-)

I am directed to invite item rates sealed quotations to undertake the work of “A/R & M/O Electric Sub-Station of Architecture Building, SPA, New Delhi.” You are requested to quote rate of the above work in the enclosed schedule of work.

The rates quoted shall include all transportation of material, labour charges, material cost, all taxes etc.

The quotations should be submitted in a sealed cover superscribed “*Quotation for A/R & M/O Electric Sub-Station of Architecture Building, SPA, New Delhi.*” All quotations must reach the undersigned on or before 27.12.2011 upto 02:00 p.m. The quotations shall be opened on the same day at 03:00 p.m. in the Purchase, Store and Maintenance Section of the School.

The department reserves the rights to reject / accept any or all the quotations without assigning any reasons thereof.

Thanking you,

Yours faithfully,

Sd/-
(SUSHILA RANI)
ASSISTANT REGISTRAR

Encl.: Schedule of work

To,

SCHOOL OF PLANNING AND ARCHITECTURE: NEW DELHI
4, Block – B, I.P. Estate, New Delhi – 110 002

Ref. No.: F.1-73/11-12/SPA(PSM)

December 19, 2011

Date of opening: 27.12.2011 at 03:00 p.m.

SCHEDULE OF WORK

Name of work: A/R & M/O ELECTRIC SUB – STATION OF ARCHITECTURE BUILDING, SPA, NEW DELHI (ESTIMATED COST: Rs.30,666/-)

(In Rupees)

S.No.	Description	Qty.	Unit	Rate	Amount
1.	Providing and fixing 1 mm thick M.S. sheet door with frame of 40 x40x6mm angle iron and 3mm MS gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer. Using M.S. angles 40 x40x6mm for diagonal braces.	3.36	Sqm		
2.	Supplying and fixing rolling shutters of approved make, made of required size MS laths interlocked together through their entire length and jointed together at the end by end locks mounted on specially designed pipe shaft with brackets, side guides and arrangement for inside and outside locking with push and pull operation complete including the cost of providing and fixing necessary 27.5cm long wire springs grade No.2 and M.S. Top cover of required thickness for rolling shutters. 80x 1.20mm MS laths with 1.20 mm thick top cover.	13.50	Sqm		
3.	Providing and fixing ball bearing for rolling shutters.	6	Each		
4.	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary requires to scratches etc. complete.	50.0	Sqm		
5.	Distemping with 1 st quality acrylic washable distemper (ready mixed) of approved manufacturer and of required shade and color complete as per manufacturer's specification. Two or more coats on new work	84.70	Sqm		
6.	White washing with lime to give an even shade: Old work (two or more coats)	35.28	Sqm		
Sub Total:					

P.T.O.

S.No.	Description	Qty.	Unit	Rate	Amount
B/F:					
7.	Finishing walls with water proofing cement paint of required shade: Old work (one or more coats applied @ 2.20 kg /10 sqm) over priming coat of primer applied @ 0.80 littrs /10 sqm complete including cost of Priming cost.	94.99	Sqm		
8.	Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 metres lead: Or area beyond 3 sq. metres.	3	each		
9.	Painting with synthetic enamel paint of approval brand and manufacture to give an even shade: Two or more coats on new work.	35.10	Sqm		
10.	Renewing glass panes, with putty and nails wherever necessary: Float glass panes of thickness 4mm	3.75	Sqm		
11.	Providing and fixing pressed steel door window and ventilators of mild steel Tee- sections, joints mitred and welded with 15 x3 mm lugs 10cm long embedded in cement concrete blocks 15 ×10×10 cm of 1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size) or with wooden plugs and screws or rawl plugs and screws or with dash fastener or with fixing clips or with bolts and nuts as required including fixing or necessary butt hinges and screws and applying a priming coat of approved steel primer.	33.90	Kg		
Total:					

(Rupees _____ only)

Terms & Conditions:

- The work shall be completed within 15 (fifteen) days from the date of issue of work order otherwise 1% penalty per day upto a maximum of 10% shall be imposed on gross amount of bill.
- 2% Income Tax will be deducted from the bill.
- The work will be carried out as per manufacture specification and entire satisfaction of Engineer-in-Charge.

Seal, Signature, complete address &
Telephone nos. of the Contractor

Sd/-
(T.S. GAUTAM)
Consultant Engineer (Civil)