

SCHOOL OF PLANNING AND ARCHITECTURE: NEW DELHI
4, Block – B, I.P. Estate, New Delhi – 110 002

Ref. No.: F.1-76/11-12/SPA(PSM)

December 19, 2011

Date of opening: 29.12.2011 at 03:00 p.m.

NOTICE INVITING QUOTATION

Name of work: PROVIDING, INSTALLATION, TESTING AND COMMISSIONING OF CCTV SYSTEM AT LIBRARY, STUDIO NO.1 & 2 OF 3RD FLOOR AND COMPUTER LAB OF ARCHITECTURE COMPLEX (ESTIMATED COST: RS.1,84,350/-)

Sealed quotations are invited from contractors for the following work:

S.NO.	DESCRIPTION OF WORKS	ESTIMATED COST (IN RUPEES)	EARNEST MONEY (IN RUPEES)
1.	Removing of dampness problem in Administrative Office, Planning Building of the School.	1,84,350/-	4,600/-

The contractors are requested to quote their lowest/competitive item rates in the enclosed Schedule of Work. The rates quoted shall include all transportation of material, labour charges, material cost, all taxes etc. The quotation shall be accompanied by earnest money of Rs.4,600/- in shape of DD/Manager's Cheque in favour of "School of Planning and Architecture, New Delhi."

The quotations should be submitted in a sealed cover superscribed "Providing, installation, testing and commissioning of CCTV System at Library, Studio No.1 and 2 of 3rd Floor and Computer Lab of Architecture Complex of the School." All quotations must reach in the office of the undersigned (PSM Section) on or before 29.12.2011 at 02:30 p.m. The quotations shall be opened on the same day at 03:00 p.m. in the presence of such contractors/ representatives who wish to remain present.

Conditional quotations/quotations not accompanied with EMD shall be summarily rejected. The Department reserves the rights to reject/accept any or all the quotations without assigning any reasons thereof.

Sd/-
(SUSHILA RANI)
ASSISTANT REGISTRAR

Encl.: Schedule of work

To,

SCHOOL OF PLANNING AND ARCHITECTURE: NEW DELHI
4, Block – B, I.P. Estate, New Delhi – 110 002

Ref. No.: F.1-76/11-12/SPA(PSM)

December 19, 2011

Date of opening: 29.12.2011 at 03:00 p.m.

SCHEDULE OF WORK

Name of work: PROVIDING, INSTALLATION, TESTING AND COMMISSIONING OF CCTV SYSTEM AT LIBRARY, STUDIO NO.1 & 2 OF 3RD FLOOR AND COMPUTER LAB OF ARCHITECTURE COMPLEX (ESTIMATED COST: RS.1,84,350/-)

(In Rupees)

S.No.	Description	Qty.	Unit	Rate	Amount
1.	Supply, installation, testing and commissioning of 16 Channel DVR having features of H.264 compression, 400 FPS per camera Rec/400fps, Live recording/Playback Pan/ tilt/ Zoom function, Speed Doom Control, Network Functionality, Remote Accessibility through/IP/ARP, DHCP, USB Port and support 4-SATA Port Storage support upto 16 TB NO HDD, of make SAMSUNG cost of work includes all required accessories such as BNC, Connector etc. to complete the work.	01	No.		
2.	Supply, installation, testing and commissioning Fixed dome heavy duty camera 1/3ö Sony super CCD, 540 TV Lines 0.3 Lux SSNR, 3mm Fixed Lens, Compact light weight and stylish Design DC 12V, make SAMSUNG cost of work include all required accessories such as BNC Connector etc. to complete the work.	16	No.		
3.	Providing, installation, testing and commissioning of Hard Disk 2 Nos. of one month back up data recording 500 GB as required at site.	02	No.		
4.	Power supply (SMPS) 12V, DC, 2 Amp for fixed doom camera of make (ITPL) ISI mark	04	No.		
5.	Supply and installation of heavy duty PVC casing and capping/conduit on surface including all accessories, T-joint, internal and external bend and straight joint, fixing, etc. including chasing the wall/floor and plastering the chased portion and making good the damage if any etc. complete as required: a) 25mm	250	RM		
Sub Total:					

P.T.O.

(In Rupees)

S.No.	Description	Qty.	Unit	Rate	Amount
B/F:					
6.	Supply and drawing of following size of cable in existing conduit/casing capping, cable tray and raceways etc. include connections and termination etc. as required at site:				
a)	Coaxial cable RG 6	300	RM		
b)	2 core 0.5mm, 12 volt CU Cable PVC insulated	250	RM		
7.	Supply and installation of 21 inch LCD monitor of make SAMSUNG/LG/SONI	1	No.		
Grand Total:					

(Rupees _____ only)

Terms & Conditions:

- The work shall be completed within 01 (one) month from the date of issue of work order otherwise 1% penalty per day upto a maximum of 10% shall be imposed on gross amount of bill.
- 2% Income Tax will be deducted from the bill.
- The work will be carried out as per manufacture specification and entire satisfaction of Engineer-in-Charge.

*Seal, Signature, complete address &
Telephone nos. of the Contractor*

Sd/-
(M.P. SINGH)
Consultant Engineer (Electrical)