

4, Block B, I.P. Estate, New Delhi 110 002

Date:23/09/26

NOTICE INVITING QUOTATION

Percentage rate of **quotations** are invited for the work:- **Minor improvement and beautification of entrance area of Girls Hostel at Planning Block SPA, New Delhi.**

Therefore, you are hereby requested to quote your rate for the above cited work in the attached schedule of work & in Annexure format.

The rates quoted by you shall inclusive all transportation of material, labour charges, material cost, all other taxes & duties etc. Nothing will be pay extra beyond the said work. Additional/Extra work beyond the permissible limit will be pay after the approval of competent authority of the School. The work will be executed as per CPWD specification and norms.

The contractor shall inspect the site before quoting the rates and it will be sole responsibility of the contractor to making all safety arrangement of the incumbent of the school, students, and the labour.

The School reserves the rights to reject / accept any or all the quotations without assigning any reasons thereof, Participate agency must have valid license of C.P.W.D.

The quotations should be submitted in a sealed cover subscribing name of the work and agency address. All quotations must reach the undersigned on 28/09/26 before 1.00 P.M. The quotations may be opened on the same day.

The School reserves the right to assign the work to one or more agencies at any stage at the agency's risk and cost in case the agency does not complete the work on the prescribed date and time. Incomplete and conditional quotations/tenders will be rejected.

Thanking you,

Yours faithfully

Junior Engineer

Consultant engineer

11
23/9/2026

Encl.. Schedule of work

Head CASS - To Publish The NIO on SPA web portal.

Minor Improvement and Beautification of Entrance Area of Girls Hostel at Planning Block, SPA, New Delhi

			UNIT	QUANTI	RATE	AMOUNT
13.91	1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	sqm	65	25.15	1634.75
13.8	2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	sqm	65	156.05	10143.25
13.41.1	3	13.41 Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade : New work (two or more coats) over and including water thinnable priming coat with cement primer	sqm	65	185.65	12067.25
9.133.2.1	4	9.133.2 Multipurpose cement board reinforced with suitable fibre cement screw 8 mm thick cement fibre board as per IS : 14862	sqm	40	1443.45	57738.00
26.22.1	5	26.22 Providing and fixing false ceiling at all heights with integral densified calcium silicate reinforced with fibre and natural filler false ceiling tiles of Size 595x595mm of approved texture, design and patterns as per CPWD Specification 2019, to be laid in true horizontal level suspended on inter-locking metal T-Grid of hot dipped galvanised iron section of 0.33mmthick (galvanized @ 120 grams per sqm including both sides) comprising of main-T runners of size 24x38 mm of length 3000 mm, cross - T of size 24x32 mm of length 1200 mm and secondary intermediate cross-T of size 24x32 mm of length 600mm to formgrid module of size 600 x 600 mm, suspended from ceiling usinggalvanised mild steel items (galvanizing @ 80 grams per sqm) i.e. 12x50 mm long dash fasteners, 6 mm dia fully threaded hanger rod upto 1000 mm length and L-shape level adjuster of size 76x25x25x1.6 mm fixed with grid and Z cleat of size 25x37x25x1.6mm thick with precut hole on both 25mm flange to pierce into 12x50mm or even bigger size dash fastener if require, fixed with Glavanised iron perimeter wall angle or size 24x24x0.40 mm of length 3000 mm to be fixed on periphery wall / partition with the help of plastic rawl plugs at 450mm center to center and 40 mm long dry wall S.S screws. The workshall be carried out as per specifications, drawing and as per directionsof the Engineer-in- Charge. With 15 mm thick Tegular edged light weight calcium silicate false ceiling tiles	sqm	23	2207	50761.00
1745	6	Supply & Fixing of Square type 2'x2' LED Panel Light 36W, Recess Mount Type Natural White Color or Cool Day White ,Square Shape, Lumen output 3600 Lm, Body material Steel Sheet plus PC diffuser, Cutout Size 24x24 inch, 2x2 Grid Panel Backlight, Lumen, High Uniformity & CRI>80 , Efficiency 100 lm/W ,Compact integral design ,Multiple Lumen Packs & CCT Suiting Different Applications and Heights Super Slim With Just 35mm Depth Inside Ceiling 25000 hrs Ambient Temperature 45°C Surge 2.5 KV Internal, Operating Voltage 160-270V, THD <30% Uv Stabilised frame with uniformly diffused light due to high quality PC diffuser easily serviceable ballast Warranty for free replacement (1Years) Recess Mount type : Make: crompton, Havells, Philips	Each	4	5252	21008.00
M/R	7	Providing and fixing of roller blind with necessary arrangement for fixing of blind complete (including Control unit, Idler, Head rail, Bottom rail, operating chain, Fixing brackets & clamps, roller tube etc as per site requirement and direction of engineer-incharge.) and fabric with the following specifications: 1) Composition: 3 Ply PVC+1 Ply Fiber Glass Black out 2) Coating: 1 Ply Fiber Glass Blackout 3) Weight: 520Gsm 4) Fabric Width: as per window width 5) Tearing Strength: 64 N Warp, 57 N Weft 6) Thickness:0.36 mm 7) Environmental Certificate: Green Guard	sqm	3	3637	10911.00
		TOTAL AMOUNT				164263.25
		Terms& Conditions				
1		The work shall be completed with in 05 Days froms the date of issue of work order otherwise 1% penalty per day up to a maximum of 10% shall be imposed on gross amount of bill.				
2		2 % income tax will be deducted from the bill.				
3		The work shall be carried out as per C.P.W.D. specification and entire satisfaction of engineer-in-charge.				
4		1% Water Charges will be deducted from the bill.				
5		1% Labour Cess will be deducted from the bill.				
					AE (Civil)	